

## Proposed construction of ASTC Ticket Counter at LGBI Airport, Borjhar, Guwahati

SL. NO	SOR NO	Description of Items	Unit	Quantity	Rate & in word	Amount & in word
1	<b>STRUCTURAL STEEL WORKS</b>					
	10.16	Steel work in built up tubular (round, square or rectangular hollow tubes etc.) etc, including cutting hoisting, fixing in position and applying a priming coat of proved steel primer, including welding and bolted with special shaped washers etc. complete				
	10.16.1	Hot Finished welded types tubes	Kg	320		
2	<b>WOOD WORK/ HARDWARES</b>					
	9.20.1	Providing and fixing ISI marked flush door shutters conforming to IS:2202 (Part I) decorative type,core of block board construction with frame of 1st class hard wood and well matched teak 3 ply veneering with vertical grains or cross bands and face veneers on both faces of shutters. 35mm thick including ISI mark stainless steel butt hinges with necessary scrwes.	Sqm	2		
	9.74	providing and fixing bright finish brush towel bolts ( Barrel type) with necessary screws ets. Complete:				
	9.74.1	250x10mm	each	2		
	9.75	Providing and fixing bright finished brass door latch with necessary screws etc.complete:				
	9.75.1	300x16x5mm	each	1		
	9.76	Providing and fixing bright finished brass 100mm mortice latch and lock with 6 levers and a pair of lever handles of approved quality with necessary screws etc. Complete	each	1		
	9.81	Providing and fixing bright finished brass handles with screws etc.Complete				
	9.81.1	125mm	each	1		
	9.82	Providing and fixing bright finished brass hanging type floor door stopper with necessary screws,etc. complete	each	1		
3	<b>FLOORING ETC.</b>					
		Providing and laying PVC tile flooring of approved brand ,in all colours and shades , laid on 20mm thick BWP plyboard,which is fixed on floor etc.,Complete	Sqm	6		

**FALSE CELING**

12.52	<p>Providing and fixing tiled false ceiling of specified materials of size 595x595 mm in true horizontal level, suspended on interlocking metal grid of hot dipped galvanized steel sections (galvanized @ 120 grams/sqm, both side inclusive ) Consisting of main "T" runner with suitably spaced joints to get required length and of size 24x38 mm made from 0.30 mm thick (minimum) sheet, spaced at 1200mm center to center and cross "T" of size 24x25 mm made of 0.30 mm thick (minimum) sheet 1200mm long spaced between to the angle hanger of 25x10x0.50 mm of required length with nuts &amp; bolts of required size and other end of angle hanger fixed with intermediate G.I channel 45x15x0.9 mm running at the spacing of 200 mm centre to centre, to which the ceiling section 0.5 mm thick bottom wedge of 80 mm with tapered flanges of 26 mm each having lips of 10.5 mm, at 450 mm centre to centre, shall be fixed in a direction perpendicular to G.I. intermediate channel with main "T" at 600 mm centre to centre to form a grid of 1200x600 mm and secondary cross "T" of length 600 mm and size 24x25 mm made and size 24x25 mm made of 0.30 mm thick</p>				
12.52.1	<p>GI Metal ceiling Lay in plain Tegular edge Global white colour tiles of size 595x595 mm, and 0.5mm thick with 8mm drop; made of G I sheet having galvanizing of 100 gms/sqm ( both sides inclusive) and electro statically polyester powder coated of thickness 60 microns (minimum), including factory painted after bending.</p>	Sqm	5		
5	<p>Providing supplying and fixing the ACP board as per specification and drawing etc complete.</p>	Sqm	17.3		
6	<p>providig , supplying and fixing the polycarbonate sheet as per specification and drawing etc complete.</p>	Sqm	2.5		
7	<p>Counter desk with locking facility as per drawing and finishing complete</p>	LS.	1		
8	<p>Electrical works including two light points, one fan point and one computer points complete.</p>	LS.	1		
9	<p>Signage System (Glow Signage)</p>	LS.	1		
10	<p>Locking with security system with CC camera's facility complete.</p>	LS.	1		